



1. Sewer generated from customers is pumped in from the pump station facility.
2. Sewer generated from the Veterans Homes flows in to the system.
3. Influent.
4. Aerated Grit Removal
5. Primary Sedimentation Tank
6. First Stage Trickling
7. Intermediate Sedimentation Trickling

8. Second Stage Trickling Filter
9. Solids Contact Basin
10. Final Sedimentation Basin
11. Fuzzy Filter
12. Chlorine Contact
13. Effluent Storage
14. Recycled Water is pumped out to customers.



*Town of Yountville*

*"The Heart of the Napa Valley"*